

## Water Supply Scheme in Baruipur Municipality

<b>Likely Impact</b>	Provision of treated surface water in Baruipur Municipality from the Water Treatment Plant of PHED at Dakshin Raipur
<b>Area Covered</b>	All the 17 wards of the municipality
<b>Population to be benefitted</b>	About 0.45 Lakh (2001) About 0.96 Lakh (Projected for design year 2039)
<b>Major Components</b>	<ul style="list-style-type: none"> <li>✓ One semi - underground reservoir of 0.25MG capacity</li> <li>✓ Clear water pumps</li> <li>✓ Booster Chlorination plant</li> <li>✓ 5 nos. of Elevated Service Reservoirs of total capacity of 2.2ML</li> <li>✓ Distribution network of about 9.2 km with DI pipes of varying diameters</li> <li>✓ 100% metering of HSC for water supply &amp; bulk meters</li> </ul>
<b>Approved Project Cost</b> (Rs in Crore)	9.52
<b>Fund Sharing</b> (Rs in Crore)	Govt of India : 3.33 GoWB : 3.33 KMDA : 2.38 ULB : 0.48
<b>Implementation Period</b>	25 months
<b>Implementing Agency</b>	KMW&SA
<b>Present Status</b>	Construction of 3 OHRs completed and 4th OHR nears completion. Laying of Conveyance Main nearing completion.